



Project Spotlights: NCMT Berth 24-10, Port of San Diego



LOCATION

San Diego, CA

COMPLETION DATE

2017

CATEGORY

Geofoam

ABOUT THE PROJECT

The existing wharf structure for the National City Marine Terminal (NCMT) required load-reduction fill material due to the increased load applied by pile cap connections on the wharf deck in order to comply with the seismic reinforcement retrofit.

THE SOLUTION

Geofoam was chosen for this project since it's the lightest fill material available and also provides excellent bearing capacity.